



PHOENIX PROJECTS PVT. LTD.

Persistently in Pursuit of Excellence

C.I.N. : U45201GJ2002PTC040615

'Phoenix House', Jalaram - 3, Ravi Ratna Road, Nr. Kohinoor Tower, off - 150 feet Ring Road, Rajkot - 360 005. (Gujarat)

E-mail : ppplraj@gmail.com

Telefax : 0281 - 2578104

Phone : (Off.) 0 98795 99943

No. PPPL/ Hafeshwar-11 /286

Date: 14/09/2018

To,

MBH Pumps (Guj.) Pvt. Ltd.

14 GIDC Industrial Estate, Naroda,

Ahmedabad,

Kind attention: Mr. Parth , <marketing@mbhpumps.com>

Sub : 2nd Revision of PURCHASE ORDER for our contract work of "Narmada River Basin (Nr. Hafeshwar) Based RWSS for Mangoi and Gollav (Package-11)" for GWSSB.

Ref : Our order No. PPPL/ Hafeshwar-11 / 004, Date: 03/01/2018 & it's 1st revision dated 15/05/2018

Dear Sir,

As per your mail dtd 08/09/2018, we are palcing herewith the 2nd Revision of PURCHASE ORDER as under.

Sr No	Item	Discharge Cum/Hr	Head (Mtr)	Minimum KW	Minimum Pump Efficiency	Qty	Rate/ Set	Amount Rs.
1	Horizontal Split case type pumps with suitable TEFC squirrel cage induction motor working on three phase 50 Hz +/- 5%, 415 V +/- 10% along with Base Frame, coupling with guard, Foundation bolts etc. as per relevant IS, following MoC and as per detailed Tender specification Impeller with wearing ring- Bronze, shaft with sleeve- S.S., Casing - D.I., Base frame - M.S., each Pumps with mechanical seal.	165.00	70	55.00	As per the approved QAP	2		
2	As above	89.00	46.00	18.50		2		
3	As above	153.00	44.00	30.00		2		
4	As above	50.00	53.00	18.62		2		
5	As above	194.00	33.00	30.00		2		
6	As above	168.00	62.00	45.00		3		
7	As above	336.00	44.00	75.00		2		
8	As above	72.00	31.00	15.00		2		
9	Monoset Submersible Pumpset (water immersed) 3 phase, 50 Hz, +/- 5%, 415V +/- 10% along with suitable foundation / installation device and cable as per detailed tender specification	51.00	39.00	11.00	As per the approved QAP	2		
10	As above	24.00	24.00	5.50		2		
11	As above	32.00	70.00	15.00		2		
	Total							
	Discount offered by Mr. Parth	i.e. Same as per the previous order.						
	Net amount Rs.							

Terms and Conditions.

1. GST payable extra.
2. Freight payable extra. Packing forwarding charges are included.
3. Approval of Data sheets/Drawings/QAP and Inspection Clearance by TPI/Client is necessary.
4. Delivery period: 90 days from the date of approval of Data sheets/Drawings/QAP.



PHOENIX PROJECTS PVT. LTD.

Persistence in Pursuit of Excellence

Phoenix House, Jalaram - 3, Ravi Ratna Road, Nr. Keshinor Tower, off - 150 feet Ring Road, Rajkot - 360 005. (Gujarat)
 E-mail : ppprl@gmail.com Telephone : 0281 - 2578104 Phone : (Of.) 0 90990 84255 Date: 17/07/2017
 No. PPPL/Morbi-1-WSS/257

To,
 MBH Pumps (Guj.) Pvt. Ltd.

14 GIDC Industrial Estate, Naroda,
 Ahmedabad.

Kind attention: Mr. Parth <marketing@mbhpumps.com>

Sub: PURCHASE ORDER for our contract work of:

"Morbi Water Supply Scheme (Package-I)", for G-VSSB.

Ref: Your quotation No. 145260 (REVISED) dated 12/07/2017 and verbal discount thereon.

Dear Sir,

With reference to the above, we are pleased to place purchase order for items as under.

Sr No	Item	Quantity	Unit	Rate Rs./Set	Amount Rs.
1	HSCF Pump set with Motor, Mechanical seal, Base Frame, Coupling, Coupling Guard and all the specified accessories. MODEL : MBH H 200 - 250 - 360 i.e. Horizontal split casing centrifugal Pumpsets of required capacity and head with suitable TEFC squirrel cage induction motor working on three phase 50Hz, 33, 415 V +/- 10% along with base frame, coupling with guard, foundation bolts etc. complete set as per relevant IS and following M.O.C. Impeller with wearing SS, Shaft with sleeve S.S., Casing-C.I., base frame MS. Discharge of each Pump 30 - 34 m ³ /hr Head (H) = 39 mtr. Motor rating 55 kW (min.). Pump eff. = 79 % (min.)	3	Set		
	Total				

Note: This order is subject to Clients approval to Data sheets/Drawing/ QAP. Kindly send the same. The items shall be as per the client GWSSB's tender Specifications.
 Terms and Conditions.

1. GST @ 12% payable extra.
2. Packing, Forwarding & Freight charges up to our site at Morbi are included in the above rates.
3. Approval of Data sheets/Drawings/QAP and Inspection Clearance by TPI/Client is necessary.
4. Inspection: To be carried out before dispatch by Client/TPI at the cost of our client.
5. Supply: Between 75 to 90 days from the date of approval of Data sheets/Drawings/QAP.
6. Payment: Within 30 days from the delivery date.
7. Our GST No. 24AACCP9998F1ZW / PAN No. AACCP9998F
8. Warranty: Equipments shall be guaranteed for 18 months from the date of supply.
9. Contact person at our site : Mr. Anil Kamaria - 97243 63795/ Mr. Jasmin Bhimani 91733 08330/ Mr. Harshad Bhimani - 98255 23358
10. Place of Delivery : Nazarbaug Head Works, Near Vintage Ceramic, near Nazarbaug railway station, Morbi, Gujarat.

Thanking you
 Yours sincerely,

(Nanji Bharat Kamaria)
 Managing Director
 Phoenix Projects Pvt. Ltd.



[Handwritten signature]



VINOD H. PATEL

'AA' Class Govt. Approved Contractor

Specialist : R.C.C. U/G. SUMP, R.C.C. E.S.R., WTP, P.V.C. M.S. H.D.P.E. D.I. G.R.P. PIPE LINE

Office : F-21, Perfect Plaza, Nr. Saikrishna Hospital, Radhanpur Road, Mehsana.
Pin - 384 002. Ph. : (0) 02762 231798 (M) 98252 64232

E-mail : vinod_gorad@yahoo.co.in

To,
MBH Pumps (Guj.) Pvt. Ltd.
14 GIDC Industrial Estate, Naroda,
Ahmedabad, India 382 330

Dt. 24/01/2017

P.O. No. :- MRB-VHP/PM/MBH/88

Kind Attn: - Mr. Parth Kamaniya. Mob: - 9825467472

Sub: Purchase Order of Pumping machinery as per tender specification for below mentioned GWSSB project.

Name of Project: Designing, Constructing, Testing & Commissioning of RCC U.G. Sump, RCC ESR at different sub head works, Providing, Supplying, Lowering, Laying, Jointing, Testing and Commissioning of DI pipes for Clear Water Mains including Supply, Installation, Testing and Commissioning of Pumping Machinery with all allied work complete including post completion O&M for Five years for Morbi Water Supply Scheme (Package-II), Dist.- Morbi..

With reference to the above sited project we are please to place an order for purchase of the all type of pumps and motors as per tender specification of GWSSB approved for above project. This in reference of your quotation no: - 144268 Dated 02.12.2016 and personal telephonic discussion for negotiation for price and finally decided as below.

Sr.	Description	Qty.	Rate/Qty.	Total Amount
1	Supply, Installation, Testing & Commissioning of Horizontal split casing centrifugal Pumpsets of required capacity and head with suitable TEFC squirrel cage induction motor working on three phase 50HZ, +/- 3%, 415 V +/- 10% along with base frame, coupling with guard, foundation bolts etc. complete set as per relevant IS and following M.O.C. Impeller with wearing SS, Shaft with sleeve S.S., Casing-C.I., base frame-MS. Discharge of each Pump (Q)=101 m ³ /hr Head (H) = 33.5 mtr. Motor rating (kW) = 18.5 kW (Min.) , Pump eff. = 63 % (min.)- Kesarbaugh GSR to ESR-1	3		

Approved



Larsen & Toubro Limited, Construction.

PB No 979, Mount-Poonamallee Road, Manapakkam, Chennai - 600089, Tamilnadu, India

CIN - L99999MH1946PLC004768

SCM Purchase Order - EJ338PO0000066 - Revenue and Domestic - Dt.21-Mar-2020

Job	: LE190217 - WS - Integrated Infrastructure Development works which include Transport Circulation (Road) Road Side Plantation Arboriculture Storm Integrated Infrastructure Development works which include Transport Circulation (Road) Road Side Plantation Arboriculture	MR Number	: EJ338EMR0000159 DT: 19-Mar-2020
LST Reg No	: 0/23-Jul-2011	CST Reg No	: 0/23-Jul-2011
Our Ref	: EJ338OFR0000079 DT: 20-Mar-2020	Your Ref	: EJ338OFR0000079/1 DT: 21-Mar-2020
Vendor	: VAM00507 - MBH PUMPS (GUJ) PVT LTD 14,GIGCNARODAINDL.ESATE,, NARODA,, AHMEDABAD,, AHMEDABAD, GUJARAT, INDIA, 45676, marketing@mbhpumps.com, AAACM7934L		
Consignee Tax Identification No	: 20AAACL0140P2ZW		
Delivery Warehouse	: 5969 - INTEGRATED INFRASTRUCTURE DEVELOPMENT WORKS RANCHI SMART CITY IN THE STATE OF JHARKHAND ON EPC BASIS LARSEN&TOUBROLIMITED,RANCHISMART, CITY,PLOTNO24,BESIDEDHURWACHOWK, Ranchi, Jharkhand, India		
Delivery Period From	: 21-Mar-2020 To 30-Jun-2020	LD Clause	: Yes Price Variation : No
Delivery Term	: AT OUR SITE STORES	Payment Centre	: Shared Services Centre - Accounting Center
Remarks	: Price basis is F.O.R site and firm without any escalation till last supply. GST @ 12% shall be paid extra on the basic price. PO price is inclusive of Packing & Forwarding and Transportation Charges upto Site. Delivery should be within 8 Weeks from the date of manufacturing clearance. Warranty - 36 Months from the date of last supply against manufacturing defects.		
Payment Terms	: Stage -1. 90.00% After the Receipt of Materials 60 Days Credit By Cheque Stage -2. 10.00% After the Submission of Performance BG 0 Days Credit By Cheque - PBG shall be submitted for 10% of PO Value valid for 36 Months from the date of last supply		

Consignor Tax Registration Details

Country	: India	State	: Gujarat
Vertical	:	Tax Identification No.	: 24AAACM7934L1Z8

Material Details

Values INR
In :

#	Amd no	Std. Material Code	Std. Material Description	HSN Code	Basic Rate	Net Rate
		Stock ID	Additional Specification	UOM	Quantity	Amount
1	0	6M81M00GB	HORIZONTAL CENTRIFUGAL SPLIT CASING PUMP; TYPE OF DRIVE :- Motor driven; FLOW CAPACITY :- 91 m3/hr; HEAD :- 31 m; PRESSURE RATING :- 10 kg/cm2; POWER RATING :- 15 kW; VOLTAGE RATING :- 415 V; ROTATIONAL SPEED :- 1450 RPM; APPLICATION :- Recycling;	84137010		
		000000		Nos	3.00	



**STEEL AUTHORITY OF INDIA
LTD.**

Ispat Bhawan, Lodi Road,
New Delhi - 110003

**BHILAI STEEL PLANT
MATERIALS MANAGEMENT
DEPARTMENT**

Mailing Address:

Purchase Deptt., Ispat Bhawan
Bhilai Steel Plant, Bhilai - 490001
Fax No. 0788-2222090/ 2223491

PURCHASE ORDER

(Acceptance of Tender)

Dated : 25.02.2020

PO No. : 4140066028/19M01602260J

**To : M/s MBH PUMPS (GUJRAT) PVT
LTD
14, GIDC, NARODA INDL
ESTATE, NARODA
AHMEDABAD - 382330
Gujarat , India
GSTIN : 24AAACM7934L1Z8
V. CODE- 1000007037 SSI -
Micro**

**Quotation No : MBH11786
Quotation Date : 06.12.2019
Gem PO No :
Gem PO Date :
Our LOI No. & date :**

Copy To :

BSP GSTIN : 22AAACS7062F1ZO

Place of Business : Bhilai

Addl. Place of Business : Rajhara, Nandini, Hirri, Rowghar, BSO Bhilai

Mobile No : +91940798243

Phone No : 2861027

email id : nareshagrawal@sail-bhilaisteel.com

We are pleased to award this contract on you for supply of materials detailed in the schedule below subject to terms, conditions and instructions of this Purchase Order (PO) read along with General Conditions of Contract mentioned in (i) **SAIL - BSP:RFQ General Terms and Conditions** (ii) **BSP - Purchase Order general Conditions** and (iii) **SAIL P1** (visit our website <https://sailtenders.co.in> for these documents). Kindly acknowledge the receipt of this Purchase Order. Any discrepancy in the PO with respect to your offer may be intimated within 10 days from the date of PO otherwise it shall be presumed that the supplier has acknowledged the receipt of this PO and agrees to all the terms & conditions mentioned therein. Further please note: (1) **Timely delivery is the essence of this contract**. (2) **BSP is exempted from submission of Form-59 (road permit)**

Line No.	Item Code Item Description	Ord. Unit	Quantity Ordered	Unit Rate (INR)	Discoun per unit	Item Value(INR)	Credit Available
----------	-------------------------------	-----------	---------------------	-----------------	---------------------	-----------------	---------------------

10	602 0001000006	each	1	1000000 per each	Nil	1000000	Y
----	----------------	------	---	---------------------	-----	---------	---

PUMP, CENTRIFUGA, 500 CU. M/HR, H= 60 M

CENTRIFUGAL PUMP (WITHOUT MOTOR) # 1. PUMP TYPE : HORIZONTAL SPLIT CASING, # 2. CAPACITY : 500 CU. M/HR, # 3. HEAD : 60 M, # 4. SPEED : 1480 RPM APPROX, # 5. LIQUID HANDLED: CLEAR WATER, # 6. MAX WORKING TEMP : AMBIENT, # 7. MATERIAL OF CONSTRUCTION : # (A) IMPELLER, SHAFT SLEEVE : STAINLESS STEEL, # (B) SHAFT : FORGED CARBON STEEL, # (C) CASING: CAST IRON/STEEL, # 8. SUCTION SIZE: 200MM, # 9. DELIVERY SIZE: 150MM, # WITH COMPANION FLANGES FOR SUCTION AND DELIVERY & COUPLING (PUMP SIDE COUPLING HALF DULY MOUNTED ON SHAFT, MOTOR SIDE COUPLING HALF IN PILOT BORE)

Duties & Taxes : IGST 12.00 %

Delivery Schedule :

Budget Year	Installment No.	Quantity	Date
2020	1	1.000	By 31.05.2020

Total no. of line items: 001

Total Material Value: INR Total GST Value: INR

Terms & Conditions :

Delivery Terms : FOR BSP Stores

Mode of Despatch : By Road

FOR & ON BEHALF OF SAIL-BHILAI STEEL PLANT

**AGRAWAL NK
GM (Purchase)**

Jalkal Vibhag Nagar Nigam Varanasi

N-1610/II/ज.क.न.नि.

दिनांक- 25/02/2019

To Whomsoever it may Concern

This is to certify that M/S KMB Electricals ,Plot No 77 Manas Nagar,Durgakund,Varanasi have excuted work of Supply, Installation and Commissioning MBH Make Horizontal Split Case Pump (HSC) Of Pumping Plant machinery at Benia Zonal Pumping Station, Benia, Varanasi against Work Order no:- 1400/II/J.K.N.N, Dated 04-01-2016.

Pump Make and model no	: MBH - MBH-250/33 1,MBH-250/46
Quantity	: 02 Nos.(100 HP 01 Nos, 180 HP Nos 01)
Pump Capacity	: 11400 LPM, 15200 LPM
Head	: 27Mtr.
Motar Rating	: 100 HP, 180 HP
Value of Contract	: Rs. [REDACTED]

The pumpsets were comissioned on : 16/06/2016

This is to further certify that above pumping plant have been field tested for performace regarding capacity , head and power consumption and result were found satisfactory.

The above pump sets are running satisfactory since commisioning.

Yours faithfully


[REDACTED]
Executive Engineer
जलकष विभाग
नगर निगम, वाराणसी



GOVERNMENT OF TELANGANA
MISSION WATER & POWER DEPARTMENT
OFFICE OF THE EXECUTIVE ENGINEER, MB GRID DIVISION, MAHABUBNAGAR
(Mahabubnagar District)

Date: 25-01-2019

TO WHOMSOEVER IT MAY CONCERN

This is to certify that M/s. MBH Pumps (Gujarat) Pvt Ltd, Plot No.14, G.I.D.C, Naorda, Ahmedabad
had supplied (2) Horizontal split Casing Pump each of 100HP to Nagasala (Jadcherla) 77 MLD WTP as shown
below:

S.No.	Pump Model	Discharge (LPM)	Head (mts)	Pump Serial Number	Qty (Nos)	Date of Installation
1	MBH M350-250-375	14403	20	17110081 and 17110082	2	13.05.2018

The Performance of above pumps are found satisfactory till date.

25/01/2019
Executive Engineer,
MB Grid Division, Mahabubnagar

25/1/19



Gujarat Water Supply & Sewerage Board

(A Government of Gujarat undertaking)

3rd floor, Jalbhavan, Adajan Road, Surat

e-mail: msdmsr@gmail.com

Contact: 9978406691, 0261-2780288

DATE: 29.05.2019


TO WHOM SO IT MAY CONCERN

This is to certify that m/s MBH PUMPS (GUJI) PVT. LTD. had supplied total 08 no's HSCF Pumps through m/s VELJI RATNA JORATHIYA, Anjar in the year of 2017.
Vide agreement no. B2-02/2015-16
For the Kakrapar RWSS C package - D of Dist.: Surat

NO	MODEL	SR NO	Nos of Pumps	HP	HEAD	DISCHARGE	NAME OF SITE VILLAGE
1	MBHM200/250	17040009.10	1+1	50 HP	24 MTR	385.1 M3/H	RATOLA
2	MBHM200/250	17040007.08	1+1	75 HP	35 MTR	318.5 M3/H	KASAL
3	MBH150/200	17040005.06	1+1	60 HP	35 MTR	274 M3/H	PUNA
4	MBH65/32	17040003.04	1+1	30 HP	64 MTR	54 M3/H	KANTVA

The Performance of HSCF Pump with relevant accessories observed satisfactory for head range and discharge Pumps are working without any problem, Pumps are running good condition since last one year.

Place: - SURAT
Date: - 29.05.2019


Deputy Executive Engineer
P.H. Mech. Sub. Division
Surat

Outward no: PB/ Kakrapar /363 /2019 Dt: 29.05.2019 ✓



રાજકોટ મહાનગરપાલીકા કચેરી
દેબરભાઈ રોડ
રાજકોટ

રા.મ.ન.પા. ભાદરવા નં. 533 તા. ૧૧/૪/૨૦૧૦

TO WHOM SO EVER IT MAY CONCERN

This is to certify that Horizontal Split Casing centrifugal pump suitable for 45mtr head and 225 m3/hr discharge – 60 HP of MBH make model no. MBH M 125/150 with bonze impeller manufactured at MBH Pumps Guj. Pvt. Ltd., Ahmedabad and supplied by Marshal Trading & Co., Rajkot against the work order no. 354 dtd. 19/06/2006 for the Bhichrinaka Pumping station is running successfully till sate since installation.

SRM
11/4/10

એડી સીટી એન્જનીયર

દો. મુખ્ય સચીવ,

રાજકોટ મુનિસિપલ કોર્પોરેશન

Work order no.

354 dtd. 19/06/2006

SRM

11/4/10

દો. મુખ્ય સચીવ,

દો. નં. MBH

Guj. Pvt. Ltd., Ahm

Work order no.



DHARA ENTERPRISE



Civil Mechanical & Electrical & Pumping Goods Suppliers & All Type of Operation & Maintenance Labour Works
Govt. Approved Contractor of S.I.T.C. Works.

Ref. No. BRP/B nager/123

Date: 23/3/11

Performance – Certificate

This is to certify that MBH make Horizontal Split Casing centrifugal pump supplied to Shihor Nagarpalika with following data is running successfully till date.

Name of site :- Pumping station- 1.1, Shihor

Duty of pump :- 58 L.P.S , 30 mtrs head, 1450 rpm, 40 HP

Qty :- 01 Nos.

Performance of above pumps is satisfactory.

Dhara Enterprises
Bhavnagar.



ઝાલોદ નગર સેવા સદન

"જન સેવા ભવન"

ઝાલોદ જી હાલોદ પી.નં. ૩૮૮૧૭૦


ફોન: ૨૨૪૧૦૬ ફેક્સ નં. ૨૨૫૨૬૯ E-mail: zalod np@yahoo.co.in

જાન્યુ. એસ. એસ. વશી. / ૩૭૩૭
તારીખ :- ૧૩/૬/૨૦૧૪

TO WHOM SO EVER IT MAY CONSERN

It is certified that Horizontal Split Casing Pump with Motor of 30 HP MBH make manufacturing by MBH PUMPS (GUJ) PVT LTD plot no 14, GIDC Estate Naroda Ahmedabad supplied on date 12.08.2011 at ZALOD NAGAR SEVA SADAN work excellently without creating any trouble since the installation.




Chief Officer
Zalod Nagar Palika

S.T. NO. 0510000487
C.S.T. No. Guj 4/J/114

॥ शुद्धि प्रेरक कृष्णस्य पादपद्मं प्रसीदतु ॥

① : (ઓ) ૨૪૬૩૭૧
(૧૨) ૨૪૦૮૪૮, ૨૪૬૫૮૬
(મોબાઇલ) : ૯૮૨૫૫૨૨૩૧૩

✦ ઓર્થો ડીલર ✦

- ✦ હીલેથ કોમેન્ટરીઝ વોટર પંપ
- ✦ હોન્ડા જનરેટર તથા વોટર પંપ
- ✦ કમ્પેક્શન ગ્રીન્ડર વોટર પંપ
- ✦ વરુણ રાખગર્મીનલ પંપ
- ✦ ટેમ્પીંગન ધંતી તથા હલાર

✦ JAGAT ENGINEERING CO. ✦
જગત એન્જીનીયરીંગ કું.

મોડાસા હાઈસ્કૂલ સામે, બસ સ્ટેશન રોડ, મોડાસા- ૩૮૩ ૩૧૫ જી. સા.કં.

ગર્વમેન્ટ કોન્ટ્રાક્ટર એન્ડ સપ્લાયર્સ


09/6/2009

TO WHOMSOEVER IT MAY CONCERN

THIS IS TO CERTIFY THAT M/S MBH PUMPS (GUJ.) PVT. LTD., PLOT
NO. 14 G.I.D.C, NARODA, AHMEDABAD HAD SUPPLIED MBH-H
100/125 WITH DUTY POINTS 2520 LPM, 30 MTRS, 1450 RPM - 25 HP

THE PERFORMANCE OF ABOVE PUMP IS FOUND SATISFACTORY
TILL DATE.

For, Jagat Engineering,



Jayesh Shah

SATISFACTORY